


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
LAKE WYOLA (MA 00510). (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV MAR 79

NL

F/G 13/13

NL

END



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

2

CONNECTICUT RIVER BASIN  
SHUTESBURY, MASSACHUSETTS

AD-A155 335

LAKE WYOLA  
MA 00510

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

Copy available to DTIC users only  
permanently available to DTIC users only



DTIC  
ELECTE  
JUN 20 1985  
S G D

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

DTIC FILE COPY

MARCH 1979

DISTRIBUTION STATEMENT A  
Approved for public release  
Distribution Unlimited

85 5 28 044

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF

NEDED

JUN 04 1979

Honorable Edward J. King  
Governor of the Commonwealth of  
Massachusetts  
State House  
Boston, Massachusetts 02133

Dear Governor King:


I am forwarding to you a copy of the Lake Wyola Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Quality Engineering, the cooperating agency for the Commonwealth of Massachusetts. In addition, a copy of the report has also been furnished the owner, Town of Shutesbury, Conservation Commission, Town Hall, Shutesbury, Massachusetts 01072.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Quality Engineering for your cooperation in carrying out this program.

Sincerely yours,

  
JOHN P. CHANDLER  
Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER MA 00510	2. GOVT ACCESSION NO	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Lake Wyola  NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1979
		13. NUMBER OF PAGES 45
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Shutesbury, Massachusetts Sawmill River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  The dam is a 232 ft. long, 14 ft. high masonry embankment with a concrete spillway. The visual inspection did not disclose any findings that indicate an immediate unsafe condition. The dam has a size classification of interme- diate and a hazard condition of significant. The dam is generally in good condition. It is felt however, that certain items which are generally normal maintenance and operational procedures need attention.		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

REPRODUCED AT GOVERNMENT EXPENSE

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

BRIEF ASSESSMENT

Identification No.: 00510 MA  
Name of Dam: Lake Wyola  
Town: Shutesbury  
County and State: Franklin County, Massachusetts  
Stream: Sawmill River  
Date of Inspection: November 27, 1978

The dam is a 232 foot long, 14 foot high masonry embankment dam with a concrete spillway. The dam was originally constructed in 1883 and its primary purpose now is for recreation. The dam is owned, operated and maintained by the Town of Shutesbury Conservation Commission.

The visual inspection did not disclose any findings that indicate an immediate unsafe condition.

The dam has a size classification of intermediate and a hazard condition of significant. Based on Corps guidelines, the test flood is one half the probable maximum flood. The spillway for this dam is not capable of passing this flood without overtopping the dam by about 3 feet.


Indepth engineering data was not available and assessment is based primarily on visual inspection, past performance history, and hydrologic and hydraulic assumptions.

This dam is in generally good condition. It is felt however, that certain items which are generally normal

maintenance and operational procedures need attention. These include removal of vegetation surrounding the dam, placement of riprap on the discharge channel banks and floor, monitoring of wet areas, and establishment of a formal warning system.

The dam's spillway can pass only 16 percent of the 2870 cfs test flood outflow. The owner should engage the services of a competent consulting engineer to further evaluate the potential for overtopping and the adequacy of the spillway.

The above problems do not represent an immediate threat to the dam; however, the normal maintenance and operational procedures should be carried out by the owner over the next 2 years after receipt of this Phase I Inspection Report. The evaluation of the spillway should be carried out by the owner within one year after receipt of this Phase I Inspection Report.



*Ronald H. Cheney*  
Ronald H. Cheney, P.E.  
Associate

Hayden, Harding & Buchanan, Inc.  
Boston, Massachusetts

Lake Wyola



This Phase I Inspection Report on Lake Wyola has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

*Joseph W. Finegan*  
JOSEPH W. FINEGAN, JR., MEMBER  
Water Control Branch  
Engineering Division

*Joseph A. McElroy*  
JOSEPH A. MCELROY, MEMBER  
Foundation & Materials Branch  
Engineering Division

*Carney M. Terzian*  
CARNEY M. TERZIAN, CHAIRMAN  
Chief, Structural Section  
Design Branch  
Engineering Division

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	1/1



APPROVAL RECOMMENDED:

*Joe B. Fryar*  
JOE B. FRYAR  
Chief, Engineering Division

## CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	iii-v
Overview Photo	vi
Location Map	vii

## REPORT

### 1. PROJECT INFORMATION

1.1 General	1
a. Authority	1
b. Purpose of Inspection	2
1.2 Description of Project	2
a. Location	2
b. Description of Dam and Appurtenances	2
c. Size Classification	4
d. Hazard Classification	4
e. Ownership	4
f. Operator	4
g. Purpose of Dam	4
h. Design and Construction History	4
i. Normal Operating Procedures	5
1.3 Pertinent Data	5

### 2. ENGINEERING DATA

2.1 Design Data	10
2.2 Construction Data	10
2.3 Operation Data	10
2.4 Evaluation of Data	10

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	
3.1 Findings	12
a. General	12
b. Dam	12
c. Appurtenant Structures	13
d. Reservoir Area	14
e. Downstream Channel	14
3.2 Evaluation	15
4. OPERATIONAL PROCEDURES	
4.1 Procedures	16
4.2 Maintenance of Dam	16
4.3 Maintenance of Operating Facilities	16
4.4 Description of any Warning System in Effect	17
4.5 Evaluation	17
5. HYDRAULIC/HYDROLOGIC	
5.1 Evaluation of Features	18
a. General	18
b. Design Data	18
c. Experience Data	19
d. Visual Observation	19
e. Overtopping Potential	19
f. Dam Failure Analysis	20
6. STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	21
a. Visual Observation	21
b. Design and Construction Data	21
c. Operating Records	22
d. Post-Construction Changes	22
e. Seismic Stability	22

SectionPage


## 7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1	Dam Assessment	23
a.	Condition	23
b.	Adequacy of Information	23
c.	Urgency	23
d.	Need for Additional Investigation	23
7.2	Recommendations	23
7.3	Remedial Measures	24
a.	Operation and Maintenance Procedures	24
7.4	Alternatives	24

APPENDIXES

APPENDIX A	- INSPECTION CHECKLIST	A-1
APPENDIX B	- ENGINEERING DATA	B-1
APPENDIX C	--PHOTOGRAPHS	C-1
APPENDIX D	- HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1
APPENDIX E	- INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1





HAYDEN, HARDING & BUCHANAN, INC. U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CONSULTING ENGINEERS CORPS OF ENGINEERS  
BOSTON, MASSACHUSETTS WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

## LAKE WYOLA DAM

SHUTESBURY

MASSACHUSETTS

SCALE 1" = 5280'

DATE FEBRUARY, 1979

PHASE I  
NATIONAL DAM INSPECTION PROGRAM  
NAME OF DAM: LAKE WYOLA

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Hayden, Harding & Buchanan, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued Hayden, Harding & Buchanan, Inc. under a letter of 28 November 1978 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW 33-79-C-0012 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) Encourage and assist the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location

Lake Wyola is located in the Town of Shutesbury, in Franklin County Massachusetts. The lake is fed primarily by Skerry Brook, Tyler Brook, Plymton Brook and South Brook. The dam is located at the western shore of the lake near the community of Locks Village. The dam is shown on the Millers Falls Quadrangle, Massachusetts-Franklin County and has the coordinates of North 42° 30' 06", West 72° 26' 12".

b. Description of Dam and Appurtenances

The dam is comprised of an 82 foot long concrete spillway, a 150 ± foot stone masonry embankment, a wood frame gate house, and an outlet structure. There is also an old blocked up sluiceway contained within the embankment. The concrete spillway contains three sections and is



stepped. The right most section is 14 feet long and 1.0± feet below the top of the dam, the adjacent section is 20 feet long and 1.7± feet below the top and the 48 foot long section which is adjacent to the embankment is 3.2± feet below the top of the dam. The 2 outer sections have a plan width of about 7 feet, and the 48 foot long section has a plan width of about 18 feet. The downstream face of the spillway is rock filled. The masonry embankment is made up of 3 components. These are a central inner core wall, 16 inches thick of cemented split stone, a sand filled upstream section and a masonry downstream wall. The downstream wall has a top plan width of 7 feet and a bottom width of 10 feet and the upstream sand filling has a top plan width of 12 feet and a bottom width of 25 feet. The upstream sand filling is lined with riprap and has a typical height of about 14 feet. The gate house contains the controls for the 2 underlying sluiceway gates. The gates are steel gates with wooden shafts and the sluiceway is a 3.5 foot by 3.5 foot culvert of stone masonry. The intake is located about 20 feet upstream of the crest and has a timber grill. About 200 feet downstream of the dam is an 8 foot diameter culvert which carries water below Locks Pond Road.

c. Size Classification

The dam is classified as intermediate in size according to its storage capacity of 1565 acre feet.

d. Hazard Classification

The dam has a hazard classification of significant. At least seven habited structures located along the downstream Sawmill River could be damaged if the dam failed and loss of life could occur.

e. Ownership

The dam is owned by the Town of Shutesbury, Conservation Commission, Town Hall, Shutesbury, Massachusetts 01072.

f. Operator

The caretaker of the dam is Mr. Raymond Moriarty, the chairman of the Shutesbury Conservation Commission. His address is Old Lock's Pond Road, Lake Wyola, Shutesbury, MA 01072. Telephone- (413) 367-2670.

g. Purpose of Dam

The major purpose of the dam is for recreation. The stone culvert outlet is used to control the level of Lake Wyola. Earlier the dam serviced Lake Wyola which was used as a reservoir for the downstream mills.

h. Design and Construction History

The dam was originally designed and built in 1883. A plan of this original structure was found in the Franklin County Plan Book, Volume 3, Page 139, located in the Franklin

Commissioners office, Greenfield, Massachusetts. The old gate located near the left embankment is not shown on these original plans and was sealed in the early 1900's. The original dam was damaged by the flood of 1938 and later rebuilt.

i. Normal Operational Procedures

There is no formal operational procedure. The caretaker regulates the level of Lake Wyola on a daily basis and keeps records in a logbook located in the gate house. The lake is generally kept higher in the late spring and summer and lower in the fall and winter. If weather reports project heavy rain the caretaker opens the gates and lowers the level of the lake.

1.3 Pertinent Data

a. Drainage Areas

The drainage area of 4122 acres (6.44 s.m.) consists of wooded, hilly rural land. Several roads pass through the drainage area. Most development consists of homes surrounding the lake, (about 175 structures) Most other homes are scattered along Locks Village Road and West Road to the north of the lake. The major drainage path is Plympton Brook. It has a length of 3.2 miles and a change in elevation of about 320 feet and passes through several small ponds.

Below the dam, the outlet brooks follow a narrow valley parallel to North Leverett Road. Homes are scattered along the road, most are well above the brook, with the exception of several homes just below the dam.

b. Discharge at Dam Site

There are two outlet conduits in the dam. The principal outlet is a 3.5 foot square stone culvert with manually controlled sluice gates. The inlet has a wooden debris screen. Its capacity will vary from 15 to 224 cfs. Under tailwater conditions flow could stop. The second outlet is a three foot square stone culvert which appears to have been closed off with concrete. Some seepage has been noticed coming from this outlet. Both outlets have approximate invert elevations of 819.

The maximum known flood occurred in 1938. Part of the dam was washed out. The dam was repaired to its present form in the early 1940's. It was able to pass storm runoff from the 1955 floods without being damaged. In both cases, the amount of storm runoff at the dam was not measured.

The spillway is ungated. Assuming only the 48' and 20' sections of spillway acting as true spillways and water to elevation 832± the spillway capacity is about 450 cfs.

c. Elevation (ft. above MSL)

- (1) Streambed at centerline of dam----- (USGS) 819±
- (2) Maximum tailwater-----836.75
- (3) Upstream portal invert diversion tunnel-----none
- (4) Recreation pool-----830
- (5) Full flood control pool----- N/A
- (6) Spillway crest (ungated)-----830
- (7) Design surcharge (Original Design)-----unknown
- (8) Top Dam-----833±
- (9) Test flood design surcharge-----836±

d. Reservoir

- (1) Length of maximum pool-----3700'
- (2) Length of recreation pool-----3600'
- (3) Length of flood control pool----- N/A

e. Storage (acre feet)

- (1) Recreation pool-----1144
- (2) Spillway crest pool-----1144
- (3) Top of dam-----1703
- (4) Flood control pool-----1703
- (5) Test flood pool----- N/A

f. Reservoir Surface (acres)

- (1) Recreation pool-----104
- (2) Spillway crest-----104
- (3) Top dam-----140
- (4) Flood control pool-----N/A
- (5) Test flood pool-----176

g. Dam

- (1) Type-----Gravity, stone and concrete masonry and earth dike
- (2) Length-----230'±
- (3) Height-----14 feet
- (4) Top Width-----21 feet
- (5) Side Slopes-----approximately vertical D/S, 2:1 above water U/S
- (6) Zoning-----dry masonry, cemented core, sand fill
- (7) Impervious Core-----cemented stone
- (8) Cutoff-----unknown
- (9) Grout curtain-----unknown

h. Diversion and Regulating Tunnel-----none

i. Spillway

- (1) Type-----broad crested
- (2) Length of weir-----48' lower, 20' upper
- (3) Crest elevation-----830' lower, 831.5' upper
- (4) Gates-----none
- (5) U/S Channel-----4:1 concrete/stone
- (6) D/S Channel-----11:1 concrete/stone, 3:1 stone

j. Regulating Outlets

There is one regulating outlet. It is composed of two manually operated, wooden sluice gates on a 3.5 foot square stone conduit, passing beneath the approximate center line of the dam. A wood framed building encloses the operating

mechanisms. One gate has a rack and pinion control while the other is lever operated. The upstream invert is at approximate elevation 821.

## SECTION 2 ENGINEERING DATA

### 2.1 Design

The original dam at Lake Wyola was designed in 1883 and was called Locks Pond Reservoir Dam. The original plan was found at the Franklin County Commissioners office. This dam was damaged by the flood of 1938 and was repaired in about 1940. In depth calculations for either design were not discovered.

### 2.2 Construction

Specifications for the original 1883 dam are included with the original plan. No other construction data was discovered. A further description is included in Section 6.1.b.

### 2.3 Operation

The dam is maintained and operated by the Conservation Commission of the Town of Shutesbury. No formal operational manual for the dam exists.

### 2.4 Evaluation

#### a. Availability

The original dam plans and specifications were made available at the Franklin County Commissioners office, Greenfield, Massachusetts. State Inspection Reports for the years of 1970, 1973 and 1976 were made available at the Department of Environmental Quality Engineering Division of Waterways office in Boston, Massachusetts.



b. Adequacy

The lack of indepth engineering data does not allow for a definitive review. Therefore the adequacy of this dam, structurally and hydraulically, can not be assessed from the standpoint of review of design calculations, but must be based primarily on the visual inspection, past performance history, and hydrologic and hydraulic assumptions.

c. Validity

The field investigation indicates changes in features from the 1883 plans. The plan and cross sectional sketches from the 1973 State Inspection Report agree with the features encountered during the field investigation.

SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General

The Phase I Inspection of this dam was made on November 27, 1978. The water behind the dam at that time was within about 2 inches of the lowest spillway (48 foot section) section.

b. Dam

Visual inspection of the dam indicated it is in generally good condition.

Only the upper few feet of the upstream slope was visible at the time of inspection. Exposed portions of the upstream slope were covered with riprap and in some areas, brush was growing through the riprap.

The crest of the dam is shown in Photo 7. No evidence of vertical or horizontal misalignment of the dam could be discerned from the crest.

The downstream face of the dam consists of hand placed, typically flat, dry stone masonry in good condition.

The downstream face is at a slight angle with the vertical as shown in Photo 13. Several large trees were observed growing near the downstream face as shown in photos 4 and 5.

c. Appurtenant Structures

Structures along the dam include (1) a spillway section near the right abutment, (2) an operating sluiceway near the center of the dam, (3) an inoperative sluiceway near the left abutment and (4) a gatehouse.

The concrete covered masonry spillway was in good condition with only minor spalling. Some trees having diameters to 2 feet were observed adjacent to the spillway. A pool of unfrozen water at the base of the spillway, shown in photo 2, indicates water is seeping from the base of the spillway. Seepage was observed through riprap downstream of the concrete spillway.

Water was flowing from the operative sluiceway at the time of inspection. Some debris was observed downstream of the outlet.

The inoperative sluiceway is shown in a panoramic view, photos 4 and 5. Water was observed on the floor of the inoperative sluiceway. This water did not appear to be flowing, but a pool of water was observed downstream of the sluiceway, as shown in photo 6, indicating there is seepage from the inoperative sluiceway.

An inspection report of the dam , dated November 7, 1973, indicated the dam to be in satisfactory condition. The following wet areas were noted in the inspection report: (1) standing water inside the inoperative sluiceway,

(2) standing water in the old channel below the inoperative sluiceway, and (3) standing water in the channel below the spillway. These areas correspond to the wet areas observed during the present visual investigation. Apparently the wet areas have existed for at least five years. The wooden gatehouse was observed to be in good condition. The 2 steel gates were in working order.

d. Reservoir Area

The general area surrounding the reservoir is wooded and hilly. The shoreline is populated by small cottages. A more detailed description of the drainage area is included in Section 1.3 of this report. The amount of siltation within the reservoir is unknown.

e. Downstream Channel

The downstream channel is rock lined and wooded. The discharge channels of the spillway, operative sluiceway, and inoperative sluiceway, converge to form the downstream channel as shown in photo 3. The channel (Sawmill River) is diverted below Locks Pond Road by way of an 8 foot diameter culvert. The section of the spillway discharge channel immediately opposite the concrete apron has been eroded slightly and portions of the channel floor contain only a thin layer of stone.

### 3.2 Evaluation

Visual inspection indicates the dam and appurtenant structures to be in generally good condition. Significant findings which could, in the long term, cause problems are growth of vegetation on the upstream slope; growth of large trees near the downstream face of the dam; and lack of sufficient riprap on the downstream banks and floor of the discharge channel.

SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedure

The dam and it's outlet structure controls the water within Lake Wyola. The operator regulates the sluice gate in an attempt to maintain the water level of the lake at just over the spillway during the summer and just below the spillway during the winter. There is no formal operational procedure, however, the operator lives nearby the structure and uses his "good judgement" regarding lake and weather conditions in order to maintain the proper water level and remove surface oil caused by power boats from the lake. A log is kept to outline the daily gate activity.

4.2 Maintenance of Dam

Lake Wyola Dam is maintained by the Conservation Commission of the Town of Shutesbury. They review State reports and are responsible for instituting the recommended repairs and maintenance outlined within. Recent repairs consisted of removal of upstream tree growth and the pouring of concrete to improve the condition of the spillway. No written formal maintenance plan was disclosed for this dam.

4.3 Maintenance of Operating Facilities

The caretaker operates the outlet gates on a daily basis. No written formal maintenance plan is used less

his judgement on the performance of the facilities. The hand operated wooden shafted steel gates were in working condition.

#### 4.4 Description of Warning Systems

There are no warning systems associated with this dam.

#### 4.5 Evaluation

Although there is no formal operational procedure for the dam, the constant attention by the caretaker assures that the dam is in relatively good condition. The dam should be inspected every two years by qualified personnel who can identify conditions of concern which if left unchecked could jeopardize the safety of the dam.

SECTION 5  
HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. General

The dam has a concrete spillway with concrete end walls over the stone block masonry construction of an earlier dam. The top of dam is about 21 feet across and is earth and masonry fill. This fill extends back into the lake. The downstream face of the dam is vertical, unmortared masonry stone construction. The dam is about 14 feet high and extends across a 200 foot wide "valley" through which the outlet stream flows. The dam was apparently built originally for service to downstream mills. It is now employed basically for recreational uses since there are numerous homes and summer cottages around the lake. The dam has low surcharge storage and low spillage capacity.

b. Design Data

Nothing is known about the hydraulic design of the present dam or the original 1883 dam. Due to its location (narrow channel blocking off a large swamp-pond fed by brooks and streams) it was built at a convenient site. Many homes abutting the lake are almost at the elevation of the top of the dam.



c. Experience Data

Part of the 1883 dam was damaged in 1938. Repairs were made about 1940 to modify the dam to its present condition. Nothing is known about the severity of the 1938 or 1955 floods in this area.

d. Visual Observations

Visual observations indicated that the road culvert downstream of the dam would cause a backwater condition.

e. Overtopping Potential

The dam was investigated using  $\frac{1}{2}$  PMF criteria. This was based upon the intermediate size classification (14 foot hydraulic height and 1565 a-f storage) and significant hazard potential (7 inhabitable structures immediately below dam).

Flow through the 3.5 stone culvert would be insignificant. Flow over the spillway would be about 450cfs. This dam has a significant overtopping potential due to its low spillway capacity. To pass the test flood inflow of 4200 cfs, the dam would be overtopped by about 3 feet. The 8 foot diameter roadway culvert below the dam will cause a backwater condition to develop (capacity 600+cfs) which will increase flooding near the dam. At  $\frac{1}{2}$  PMF condition, the test flood outflow will be 2870 cfs.

This increase of water surface to 3 feet above crest of dam would have serious effects on upstream lakefront property. Serious flooding to both property and septic tanks and/or leaching fields could occur, with potential polluting of the lake ensuing.

f. Dam Failure Analysis

If the dam were to fail, with the water level at the top of the dam, the resulting outflow would be 4933. cfs. This flow would either overtop the downstream road embankment or wash it out. Between the dam and road embankment it appears that one house might have minor flooding (1 to 2 feet of water) and one home could have major damage (6 to 7 feet of water). In any case, loss of life is possible. Near the Red Brook confluence, it appears that two more homes could have major damage (4 feet of water). Loss of life could occur at both homes.

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The visual inspection did not disclose any immediate stability problems of the dam or of the appurtenant structures.

b. Design and Construction Data

Specifications of the dam from the "Franklin County Plan Book" dated November 17, 1883 indicate the dam consists of a stone wall at the downstream end and a sand filling at the upstream end.

These specifications indicate the following :

- 1) The dam is 12 feet high, 35 feet wide at the bottom, and 20 feet wide at the top.
- 2) The stone wall has an average width at the bottom of 10 feet and a top width of 7 feet.  
The stone wall is laid on hardpan.
- 3) The sand filling is 12 feet wide at the top and 25 feet wide at the bottom. The upstream slope is covered with riprap.
- 4) There is a second wall upstream of the main stone wall composed of cemented split stone 16 inches thick.

c. Operating Records

No operating records were made available.

d. Post-construction Changes

The inoperative sluiceway, near the left abutment, has been sealed since the early 1900's. Major repairs were made following the damage from the flood of 1938. Concrete was poured downstream of the spillway in 1969 to correct seepage problems.

e. Seismic Stability

The dam is located in Seismic Zone 2 according to USCE guidelines and does not require special analysis for seismic stability.

## SECTION 7

### ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

#### 7.1 Dam Assessment

##### a. Condition

The visual inspection indicates the dam to be in generally good condition. However, the spillway is not capable of passing the test flood and the dam would be overtopped.

##### b. Adequacy of Information

The information available is such that the assessment of the condition of the dam must be based primarily on the visual inspection.

##### c. Urgency

The problems associated with the remedial measures of Section 7.3 should be carried out by the owner within two years of receipt of this Phase I Inspection Report. The recommendations of Section 7.2 should be carried out by the owner within one year of receipt of this Phase I Inspection Report.

##### d. Necessity of Additional Investigations

No additional investigation is needed to complete the Phase I Inspection.

#### 7.2 Recommendations

This dam's spillway does not have the capacity to pass the 1/2 PMF test flood. The owner should engage the services of a competent Consulting Engineer to further evaluate the potential for overtopping and the adequacy of the spillway.

### 7.3 Remedial Measures

#### a. Operating and Maintenance Procedures

- (1) Vegetation on the upstream slope should be removed. All trees within 20<sup>+</sup> feet of the downstream face should be removed. These trees are shown by Photos 1,3,4,5,7,8, & 13 and their approximate locations are indicated on the Plan view in Appendix B of this report.
- (2) The wet areas noted in this inspection report should be observed during routine maintenance to determine evidences of soil transport.
- (3) Riprap should be placed on the discharge channel opposite the spillway apron and on the channel floor for a downstream distance of 20 feet.
- (4) This dam should be inspected every two years by qualified personnel who can identify areas of concern which, if left unchecked could jeopardize the safety of the dam.
- (5) A formal warning system should be developed for warning downstream residents in case of emergency.

### 7.4 Alternatives

As an alternative to the recommendations in Section 7.2, the owner could operate the lake at a lower level to insure adequate storage. This level would need to be determined by an indepth hydrologic investigation by an engineer.

APPENDIX A  
INSPECTION CHECKLIST

**VISUAL INSPECTION CHECKLIST**  
**PARTY ORGANIZATION**

PROJECT Lake Wyola

DATE Nov. 27, 1978

TIME 9:15 AM

WEATHER cloudy 20°

W.S. ELEV. 830.8+ U.S.            DN.S.

PARTY:

1. Ron H. Cheney      H H & B

6. \_\_\_\_\_

2. David Vine H H & B

7. \_\_\_\_\_

3. Daniel P. LaGatta GEI

8. \_\_\_\_\_

4. Tom Keller GEI

9. \_\_\_\_\_

5. Raymond Moriarty Shutesbury

10. \_\_\_\_\_

## PROJECT FEATURE

INSPECTED BY

REMARKS

1. Embankment Dam

Daniel P. LaGatta

## 2. Spillway

Ron H. Cheney.

### 3. Intake Structure and Gatehouse

Ron H. Cheney

4. \_\_\_\_\_

5. \_\_\_\_\_

6. \_\_\_\_\_

7. \_\_\_\_\_

8. \_\_\_\_\_

9. \_\_\_\_\_

10. \_\_\_\_\_

38



# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola DATE Nov. 27, 1978  
 PROJECT FEATURE Stone Wall/Earth Dam NAME Ron Cheney  
 DISCIPLINE Structural Engineer NAME Daniel P. LaGatta  
Geotechnical Engineer

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	833
Current Pool Elevation	A few inches below top of spillway.
Maximum Impoundment to Date	Unknown
Surface Cracks	None of significance observed.
Pavement Condition	No pavement.
Movement or Settlement of Crest	None observed.
Lateral Movement	None observed.
Vertical Alignment	No vertical misalignment observed.
Horizontal Alignment	No horizontal misalignment observed.
Condition at Abutment and at Concrete Structures	Good.
Indications of Movement of Structural Items on Slopes	None observed.
Trespassing on Slopes	None of significance.
Sloughing or Erosion of Slopes or Abutments	None of significance.
Rock Slope Protection - Riprap Failures	Small brush in riprap on upstream face.
Unusual Movement or Cracking at or Near Toes	None observed.
Unusual Embankment or Downstream Seepage	Seepage observed through riprap downstream of spillway section; seepage observed about 10' downstream of inoperative outlet channel (see text).
Piping or Boils	None observed.
Foundation Drainage Features	None found.
Toe Drains	None found.
Instrumentation System	None found.
Vegetation	Trees to 24" diam. next to downstream face of dam.

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola

DATE Nov, 27, 1978

PROJECT FEATURE Intake Structure

NAME Ron H. Cheney

DISCIPLINE Structural Engineer  
Geotechnical Engineer

NAME Daniel P. LaGatta

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p>	<p>There is no intake channel for this facility.</p> <p>The intake structure is located approximately 20' upstream of the dam. It was under water during inspection and could not be observed.</p>

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola

DATE Nov. 27, 1978

PROJECT FEATURE Outlet Works

NAME Ron H. Cheney

DISCIPLINE Structural Engineer  
Geotechnical Engineer

NAME Daniel P. LaGatta

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - CONTROL TOWER</u></p> <p>a. Concrete and Structural</p> <p>General Condition</p> <p>Condition of Joints</p> <p>Spalling</p> <p>Visible Reinforcing</p> <p>Rusting or Staining of Concrete</p> <p>Any Seepage or Efflorescence</p> <p>Joint Alignment</p> <p>Unusual Seepage or Leaks in Gate Chamber</p> <p>Cracks</p> <p>Rusting or Corrosion of Steel</p> <p>b. Mechanical and Electrical</p> <p>Air Vents</p> <p>Float Wells</p> <p>Crane Hoist</p> <p>Elevator</p> <p>Hydraulic System</p> <p>Service Gates</p> <p>Emergency Gates</p> <p>Lightning Protection System</p> <p>Emergency Power System</p> <p>Wiring and Lighting System</p>	<p>There is an 11½ ft. x 9½ ft. wood gatehouse on a concrete base located at the center of the embankment. Visual inspection indicated the concrete and gatehouse to be in good condition, with no signs of poor alignment or weathering.</p> <p>Slide gates are manually operated with rack and pinion control. Gate was operated during our inspection and appeared to be in good condition.</p>

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola DATE Nov. 27, 1978  
 PROJECT FEATURE Outlet Works NAME Ron H. Cheney  
 DISCIPLINE Structural Engineer NAME Daniel P. LaGatta  
Geotechnical Engineer

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>  General Condition of Concrete Rust or Staining on Concrete Spalling Erosion or Cavitation Cracking Alignment of Monoliths Alignment of Joints Numbering of Monoliths	There is no transition and conduit for this facility.

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola DATE Nov. 27, 1978  
 PROJECT FEATURE - Outlet Works NAME Ron H. Cheney  
 DISCIPLINE Structural Engineer NAME Daniel P. LaGatta  
Geotechnical Engineer

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	The outlet structure is comprised of the gatehouse and slide gates and the 3½' x 3½' masonry outlet box. All appear to be in good condition.
Rust or Staining	
Spalling	
Erosion or Cavitation	
Visible Reinforcing	
Any Seepage or Efflorescence	
Condition at Joints	
Drain holes	None observed.
Channel	
Loose Rock or Trees Overhanging Channel	None - Some debris near exit box.
Condition of Discharge Channel	Good.

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola DATE Nov. 27, 1978  
 PROJECT FEATURE Spillway NAME Ron. H. Cheney  
 DISCIPLINE Structural Engineer NAME Daniel P. LaGatta  
Geotechnical Engineer

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	There is no approach channel for this facility.
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Approach Channel	There is a concrete wall between the dam embankment and the spillway. There is a stone wall at the right edge of the spillway. Both appear to be in good condition with only minor weathering. The spillway had some spalling of the concrete.
b. Weir and Training Walls	
General Condition of Concrete	
Rust or Staining	
Spalling	
Any Visible Reinforcing	
Any Seepage or Efflorescence	There is rock fill downstream of the spillway. There are several trees to 24 " diameter located downstream of the spillway. Some large stones are in the channel. The general condition of the floor was good.
Drain Holes	
c. Discharge Channel	
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Channel	
Other Obstructions	

# PERIODIC INSPECTION CHECKLIST

PROJECT Lake Wyola DATE Nov. 27, 1978  
 PROJECT FEATURE Service Bridge NAME Ron H. Cheney  
 DISCIPLINE Structural Engineer NAME Daniel P. LaGatta

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SERVICE BRIDGE</u> a. Super Structure Bearings Anchor Bolts Bridge Seat Longitudinal Members Underside of Deck Secondary Bracing Deck Drainage System Railings Expansion Joints Paint b. Abutment & Piers General Condition of Concrete Alignment of Abutment Approach to Bridge Condition of Seat & Backwall	There is no service bridge for this facility.

APPENDIX B  
ENGINEERING DATA



LIST OF AVAILABLE ENGINEERING DATA

Original Plan and Specifications Dated 1883

Location: Franklin County Commissioners Office  
Main Street  
Greenfield, Massachusetts 01301

No additional information was located

*Lake Wyola*



# The Commonwealth of Massachusetts

EXECUTIVE OFFICE OF ENVIRONMENTAL AFFAIRS  
DEPARTMENT OF ENVIRONMENTAL QUALITY ENGR.  
DIVISION OF WATERWAYS

100. Nashua Street, Boston 02114

Town of Shutesbury

Town Hall

Shutesbury, Ma.

Conservation Commission

ATTN: Mr. R. Moriarty

February 15, 1977

Re: Inspection Dam #2-6-272-2  
Lock's Pond or Lake Wyola Dam  
Shutesbury, Ma.

Dear Sir:

On May 12, 1976, an Engineer from the Massachusetts Department of Public Works made a visual inspection of the above dam. Our records indicate the owner to be the Town of Shutesbury. If this information is incorrect, will you please notify this office.

The inspection was made in accordance with the provisions of Chapter 253 of the Massachusetts General Laws as amended (Dams Safety Act). Chapter 706 of the Acts of 1975 transferred the jurisdiction of the so-called "Dams Safety Program" to the Commissioner of the Department of Environmental Quality Engineering.

The results of the inspection indicate that this dam is ~~conditionally~~ <sup>safe</sup>. The following conditions were noted that require attention:

Brush and trees at base of dam and upstream slope should be removed. Minor spalling of concrete on the northerly abutment and training wall, surface cracks in the concrete apron around base of gate house. These conditions should be corrected.

We call these conditions to your attention before they become serious and more expensive to correct. With any correspondence please include the number of the dam as indicated above.

Very truly yours,

John T. Hannon, P.E.  
Chief Engineer

Re: Inspected 2-16-77  
DGE Dist 2  
DDZ Dist 2

## INSPECTION REPORT - DAMS AND RESERVOIRS

## (1) LOCATION:

City/Town Shutesbury County Franklin Dam No. 2-6-272-2Name of Dam Lock's Pond or Lake Wyola Dam

Mass. Rect.

Topo Sheet No. 13C Coordinates: N 548,500, E 347,400

Date

Inspected by: Harold T. Shumway, On May 12, 1976 Last Inspection 11-7-73(2) OWNER/S: As of May 12, 1976per: Assessors \_\_\_\_\_, Reg. of Deeds \_\_\_\_\_, Prev. Insp. x, Per. Contact x

Town of Shutesbury

1. Conservation Commission, Town Hall, Shutesbury, Mass

Name St. &amp; No. City/Town State Tel. No.

2. \_\_\_\_\_

Name St. &amp; No. City/Town State Tel. No.

3. \_\_\_\_\_

Name St. &amp; No. City/Town State Tel. No.

CARETAKER: (if any) e.g. superintendent, plant manager, appointed by  
absentee owner, appointed by multi owners.

Mr. Raymond Moriarty, Chairman

Shutesbury Conservation Commission, Old Lock's Pond Road, Lake Wyola,

Name St. &amp; No. City/Town State Tel. No.

Shutesbury, Mass.

## (4) DATA:

No. of Pictures Taken None Sketches See description of Dam.Plans, Where Franklin County Commissioners Office files - Plan Book  
Page 139 - Nov. 17, 1883 Plan.

## (5) DEGREE OF HAZARD: (if dam should fail completely)\*

1. Minor \_\_\_\_\_

3. Severe \_\_\_\_\_

2. Moderate \_\_\_\_\_

4. Disastrous x \_\_\_\_\_Approx. 366 million gallons impoundment - would be confined to  
Comments: narrow valley for several miles - valley has 2 small settlement  
plus individual houses.

\*This rating may change as land use changes (future development).

OUTLETS: OUTLET CONTROLS AND DRAWDOWN

Northerly end of dam - chute spillway 48'W.x 1'H -  
No. 1 Location and Type: additional 20' of width-1' Higher-total drop of 7'

Controls None, TYPE: \_\_\_\_\_.

Automatic \_\_\_\_\_. Manual \_\_\_\_\_. Operative Yes \_\_\_\_\_, No \_\_\_\_\_.

Comments: Minor spalling of northerly abutment - minor spalling of crest lip

No. 2 Location and Type: 70' from south end of dam - 3.5x3.5 stone masonry slu

Controls yes, Type: 2 wood slidegates - steel slides - one gate has and pinion controls - other raised by lever.

Automatic \_\_\_\_\_. Manual X. Operative Yes X, No \_\_\_\_\_.

Comments: All controls operable per caretaker of dam

No. 3 Location and Type: \_\_\_\_\_

Controls \_\_\_\_\_, Type: \_\_\_\_\_.

Automatic \_\_\_\_\_. Manual \_\_\_\_\_. Operative Yes \_\_\_\_\_, No \_\_\_\_\_.

Comments: \_\_\_\_\_

Drawdown present Yes X, No \_\_\_\_\_. Operative Yes X, No \_\_\_\_\_.

Comments: See No. 2 above.

7. DAM UPSTREAM FACE: Slope 2:1, Depth Water at Dam 10'-12'

Material: Turf \_\_\_\_\_. Brush & ~~Trees~~ X. Rock fill X. Masonry \_\_\_\_\_. Wood \_\_\_\_\_

Other Slope covered with cobble stones.

Condition: 1. Good \_\_\_\_\_. 3. Major Repairs \_\_\_\_\_.

2. Minor Repairs X. 4. Urgent Repairs \_\_\_\_\_.

Comments: Minor brush growth on rock covered slope -

8. DAM DOWNSTREAM FACE: Slope Vertical

Material: Turf \_\_\_\_\_. Brush & Trees \_\_\_\_\_. Rock Fill \_\_\_\_\_. <sup>Dry stone</sup> Masonry X. Wood \_\_\_\_\_

Other Massive stone in wall.

Condition: 1. Good \_\_\_\_\_. 3. Major Repairs \_\_\_\_\_.

2. Minor Repairs \_\_\_\_\_. 4. Urgent Repairs \_\_\_\_\_.

Comments: Some tree growth close to toe of wall - A few of these have cut down since last inspection.

9. EMERGENCY SPILLWAY: Available ves. Needed       .

Height Above Normal Water: 1 Ft. above elevation principal overflow spillway

Width 20 Ft. Height 0.7 Ft. Material concrete

Condition: 1. Good       . 3. Major Repairs       .

2. Minor Repairs X. 4. Urgent Repairs       .

Comments: A few misplaced stones in paving in channel below conc. crest  
on northerly end.

10. WATER LEVEL AT TIME OF INSPECTION: 2 Ft. Above       . Below X.

Top Dam X F.L. Principal Spillway       .

Other       .

Normal Freeboard 3 Ft. +

11. SUMMARY OF DEFICIENCIES NOTED:

Growth (Trees and Brush) on Embankment Minor brush growth on upstream slope.

Animal Burrows and Washouts None found.

Damage to Slopes or Top of Dam None found.

surface cracks in base of gate house apron.  
Cracked or Damaged Masonry yes - Minor spalling of northerly spillway flood training wall

Evidence of Seepage Minor seepage noted in channel of old sluiceway on southern end

Evidence of Piping None found.

Leaks None found.

Erosion Minor erosion of channel below spillway.

Trash and/or Debris Impeding Flow None found.

Clogged or Blocked Spillway None found.

Other       .

## OVERALL CONDITION:

1. Safe\_\_\_\_\_.
2. Minor repairs needed   X
3. Conditionally safe - major repairs needed\_\_\_\_\_
4. Unsafe\_\_\_\_\_.
5. Reservoir impoundment no longer exists (explain)

Recommend removal from inspection list\_\_\_\_\_

## REMARKS AND RECOMMENDATIONS: (Fully Explain)

Mr. Raymond Moriarty, caretaker of the dam, was present during the inspection. This dam appears to receive constant attention and except for a light growth of brush on the upstream slope, minor spalling of concrete on the northerly abutment and flood training wall, and surface cracks in the concrete apron around base of gate house, is in good condition. The usual minor seepage areas found in past inspections are evident, but do not appear to have increased any in size. Some of the large trees growing at base of dam have been cut since last inspection and others are scheduled to be cut this season per the caretaker.

Dam appears sound and safe with only routine minor maintenance repairs needed.

HTS/bk

## INSPECTION REPORT - DAMS AND RESERVOIRS

## (1.) LOCATION:

City/Town Shutesbury County Franklin Dam No. 2-6-272-2Name of Dam Lock's Pond or Lake Wyola Dam

Mass. Rect.

Topo Sheet No. 13C Coordinates: N 548,500, E 347,400Inspected by: R. C. Salls, P.E., On Nov. 7, 1973 Date  
Last Inspection 1970(2.) OWNER/S: As of November 1972per: Assessors X, Reg. of Deeds \_\_\_\_\_, Prev. Insp. \_\_\_\_\_, Per. Contact \_\_\_\_\_

Town of Shutesbury

1. Conservation Commission, Town Hall, Shutesbury, Mass.

Name St. &amp; No. City/Town State Tel. No.

2. \_\_\_\_\_  
Name St. & No. City/Town State Tel. No.3. \_\_\_\_\_  
Name St. & No. City/Town State Tel. No.(3.) CARETAKER: (if any) e.g., superintendent, plant manager, appointed by  
absentee owner, appointed by multi owners.

Mr. Raymond Moriarty, Chairman

Shutesbury Conservation Commission, Old Lock Pond Rd., Lake Wyola, Shutesbury, MName St. & No. City/Town State Tel. No.  
Tel.: 367-2670

## (4.) DATA:

No. of Pictures Taken None Sketches See description of Dam  
Plans, Where Franklin County Commissioners Office Plan Bk. 3,  
Page 139 - Nov. 17, 1883 Plan.

## (5.) DEGREE OF HAZARD: (if dam should fail completely)\*

1. Minor \_\_\_\_\_

3. Severe \_\_\_\_\_

2. Moderate \_\_\_\_\_

4. Disastrous XComments: Large impoundment would be confined to narrow valley for several miles  
valley has 2 small settlements plus individual houses.

\*This rating may change as land use changes (future development).

6. OUTLETS: OUTLET CONTROLS AND DRAWDOWN

No. 1 Location and Type: 48' wide X 1' high chute spillway with additional 2' of width 1' higher. Total drop 7' - concrete

Controls No, TYPE: \_\_\_\_\_

Automatic \_\_\_\_\_. Manual \_\_\_\_\_. Operative Yes \_\_\_\_\_, No \_\_\_\_\_.

Comments: \_\_\_\_\_

No. 2 Location and Type: Waste sluiceway 70' from south end - 3.5 X 3.5 stone masonry sluice

Controls Yes, Type: 2 wooden slide gates - steel slides - one gate rack and pinion controls - one raised by lever

Automatic \_\_\_\_\_. Manual X. Operative Yes X, No \_\_\_\_\_.

Comments: Gate open at time of inspection. Both gate stems new 4" timber - all appeared in good condition

No. 3 Location and Type: \_\_\_\_\_

Controls \_\_\_\_\_, Type: \_\_\_\_\_

Automatic \_\_\_\_\_. Manual \_\_\_\_\_. Operative Yes \_\_\_\_\_, No \_\_\_\_\_.

Comments: \_\_\_\_\_

Drawdown present Yes X, No \_\_\_\_\_. Operative Yes X, No \_\_\_\_\_.

Comments: See No. 2 above

7. DAM UPSTREAM FACE: Slope 2:1, Depth Water at Dam 10 - 12 ft.

Material: Turf \_\_\_\_\_. Brush & Trees \_\_\_\_\_. Rock fill X. Masonry \_\_\_\_\_. Wood \_\_\_\_\_.

Other Slope covered with cobblestones

Condition: 1. Good \_\_\_\_\_. 3. Major Repairs \_\_\_\_\_.

2. Minor Repairs X. 4. Urgent Repairs \_\_\_\_\_.

Comments: Several small clumps of brush. Some deformation of slope from wave and ice action.

8. DAM DOWNSTREAM FACE: Slope Vertical.

Material: Turf \_\_\_\_\_. Brush & Trees \_\_\_\_\_. Rock Fill \_\_\_\_\_. Masonry X. Wood \_\_\_\_\_. Dry stone

Other Stone in wall massive

Condition: 1. Good X. 3. Major Repairs \_\_\_\_\_.

2. Minor Repairs \_\_\_\_\_. 4. Urgent Repairs \_\_\_\_\_.

Comments: Some trees growing close to toe of wall.



9. EMERGENCY SPILLWAY: Available Yes. Needed Yes.

Height Above Normal Water 1 Ft. above elevation principal overflow spillway

Width 20 Ft. Height 0.7 Ft. Material concrete.

Condition: 1. Good X. 3. Major Repairs \_\_\_\_\_.

2. Minor Repairs \_\_\_\_\_. 4. Urgent Repairs \_\_\_\_\_.

Comments: \_\_\_\_\_  
\_\_\_\_\_

10. WATER LEVEL AT TIME OF INSPECTION: 3 Ft. Above \_\_\_\_\_. Below X.

Top Dam X F.L. Principal Spillway \_\_\_\_\_.

Other When water is at elevation of principal spillway.

Normal Freeboard 3 Ft.  $\pm$

11. SUMMARY OF DEFICIENCIES NOTED:

Growth (Trees and Brush) on Embankment Some minor brush on top and upstream slope  
few trees near south and north end dam.

Animal Burrows and Washouts None found.

Damage to Slopes or Top of Dam None noted.

Cracked or Damaged Masonry None noted.

Evidence of Seepage Very slow seepage under concrete block in old sluiceway 40'  $\pm$   
from south end. Slow seepage from under apron spillway at  
north end. Standing water in old channel below blocked

Evidence of Piping spillway and in channel below overflow.

Leaks See above.

Erosion None noted.

Trash and/or Debris Impeding Flow None.

Clogged or Blocked Spillway No.

Other \_\_\_\_\_.

12.

## OVERALL CONDITION:

1. Safe\_\_\_\_\_.
2. Minor repairs needed   X
3. Conditionally safe - major repairs needed\_\_\_\_\_
4. Unsafe\_\_\_\_\_.
5. Reservoir impoundment no longer exists (explain)  
Recommend removal from inspection list\_\_\_\_\_

13.

## REMARKS AND RECOMMENDATIONS: (Fully Explain)

At the time of this inspection, the water level was about 0.6 foot below the elevation of the overflow spillway and one of the drawdown sluiceway gates was open. There was some slow seepage from an old sluiceway about 40 feet from the south end. This sluiceway has been blocked with a concrete plug about 8 feet i No flow could be seen here but the old channel below this spillway had standing water. Similarly, there was seepage from under the apron of the overflow spillw and water was standing in the channel below the spillway but no noticeable flow was observed. This seemed to be a normal condition of little consequence.

The concrete masonry overflow spillway appears to be in good condition, its overa width is 82 feet with the elevation of the 48 foot wide normal water level spill section 3 feet below the top of the dam, the elevation of the 20 foot wide emer- gency section 2 feet below the top and the 14 foot wide emergency section on the northerly end 1.3 feet below the top of the dam. There is a concrete apron down stream of the 7 foot crest which drops 1.5 foot in 11 feet which appears to have been placed recently. At the end of the apron there is a rock fill to the runoff channel. The caretaker, Mr. Moriarty, told us that just before the Department assumed responsibility for inspection of dams, that 14 yards of concrete had bee poured to correct seepage and leakage under the spillway.

The sluiceway gates appeared to be in good condition. The 4" X 6" timber gate stems are relatively new and both gates are operable. The caretaker maintains a log of gate operations in gate house and water is drawn down whenever rain and increased runoff is anticipated.

Except for minor brush growth and the presence of some large trees at the ends of the dam, this structure appears to be satisfactory at this time. Alignment and grade are good and the embankment's top is covered with concrete and hard-packed gravel. The owners intend to cut the trees located adjacent to the south end of the dam.

RCS/js/vk

DISTRICT 2

Submitted by R. C. Salls, P.E. Dam No. 2-6-272-2

Date November 7, 1973 ~~XXXXXX~~ Town Shutesbury

Name of Dam Lock's Pond or Lake Wyola Dam

Location: Topo Sheet No. 13 C Mass. Rect. Coordinates N 548,500 E 347,400

Provide  $8\frac{1}{2}$ " x 11" in clear copy of topo map with location of Dam clearly indicated.

At Lock's Village in northwesterly corner Shutesbury just easterly of junction of Lakeview Drive and Lock's Pond Rd.

2. Year built Rebuilt after 1938 flood Year/s of subsequent repairs 1969  
Existed in 1883

3. Purpose of Dam: Water Supply \_\_\_\_\_ Recreational Now  
Flood Control \_\_\_\_\_ Irrigation \_\_\_\_\_ Other Former reservoir for mill ponds on Sawmill River

4. Drainage Area: 8 sq. mi. \_\_\_\_\_ acres.  
Type: City, Bus. & Ind. \_\_\_\_\_ Dense Res. \_\_\_\_\_ Suburban \_\_\_\_\_ Rural, Farm 15%  
Wood & Scrub Land 85% Slope: Steep 60% Med. 30% Slight 10%

5. Normal Ponding Area: 75 Acres; Ave. Depth Max. depth 40 ft. Say 12-15  
Impoundment: 366.6 million gals.; 1125 acre ft.  
Silted in: Yes \_\_\_\_\_ No \_\_\_\_\_ Approx. Amount Storage Area \_\_\_\_\_

6. No. and type of dwellings located adjacent to pond or reservoir \_\_\_\_\_  
i.e. summer homes etc. 75+ cottages on shore. More just off shore.

7. Dimensions of Dam: Length 229'+ Max. Height 14' at sluiceway  
Freeboard 3  
Slopes: Upstream Face 2:1 stone paved slope  
Downstream Face Dry stone retaining wall vertical  
Width across top 12 to 21 ft.

8.

## Classification of Dam by Material:

Earth X Conc. Masonry X Stone Masonry X  
Backing \_\_\_\_\_ Spillway \_\_\_\_\_ Face wall \_\_\_\_\_  
Timber \_\_\_\_\_ Rockfill \_\_\_\_\_ Other \_\_\_\_\_

8A.

Dam Type: Gravity X Straight \_\_\_\_\_ Curved, Arched X Other \_\_\_\_\_  
Overflow \_\_\_\_\_ Non-overflow X

9.

## A. Description of present land usage downstream of dam:

85 to 90 % rural; 10 to 15 % urban Village of Montague

B. Is there a storage area or flood plain downstream of dam which could accommodate the impoundment in the event of a complete dam failure? Yes \_\_\_\_\_ No X

C. Character Downstream Valley: Narrow X Wide \_\_\_\_\_ Developed 5  
Rural 85 to 90% Urban 10 to 15%

10.

## Risk to life and property in event of complete failure.

No. of people 8

No. of homes 16<sup>+</sup>

No. of businesses 2 - General Stores

No. of industries 2 Type Saw mills, furniture factory

No. of utilities 2 Type Electrical and telephone pole line

Railroads None

Other dams Dan E. Glazier Dam, No. 2-6-154-3, and Lucius Graves Dam, No. 2-6-154-2, Leverett, C. J. Billing & Sons Upper Dam, No. 2-6-

Lower No. 2-6-192-4, Stratton Dam, No. 2-6-192-3, and Alexander Dam, No. 2-6-192-9, in Montague, plus several other breached structures.

Sawmill River continues through Montague Center.

11.

Attach Sketch of dam to this form showing section and plan on  $8\frac{1}{2}$ " x 11" sheet.


RCS/vk

Attachments

Locus Plan

Sketches


DAM 102-272-7  
LAKE WAHOO




XX SECTION 'A A'

DO NOT SCALE

PLAN - NOT TO SCALE





Number 192

2-6-1970

TOWN SHUTESBURY

Name Locks Pond dam

Inspection Date 1970

Owner Town of Shutesbury, Park Department

Location

Type of Pond made

Acreage

Drainage Area

Comments

Type of Dam stone masonry with earth fill on the upstream side

Length 200 feet

Height 13 feet

Head of Water

Comments

Type of Spillway

Width


Height

Comments

Condition, Previous Report, Dated 1969 This dam is safe


Present Condition





APPENDIX C  
PHOTOGRAPHS

# LAKE WYOLA



HAYDEN, HARDING & BUCHANAN, INC US ARMY ENGINEER DIV NEW ENGLAND  
CONSULTING ENGINEERS CGRPS OF ENGINEERS  
BOSTON, MASSACHUSETTS WALTHAM, MASS

## NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS LOCATION OF PHOTOGRAPHS LAKE WYOLA

SHUTESBURY

MASSACHUSETTS

SCALE NOT TO SCALE

DATE FEBRUARY, 1979




PHOTO NO. 1 - Upstream portion of dam as viewed from right abutment area.



PHOTO NO. 2 - Pool of water at base of spillway. Seepage observed coming from riprap (not frozen).

PHOTO NO. 3 - View of spillway discharge channel. Note trees on bank.





PHOTOS NO. 4 & 5 - Downstream face of dam, from left abutment  
area showing inoperative sluiceway.



PHOTO NO. 6 - View of wet  
area in channel downstream  
of inoperative sluiceway.



PHOTO NO. 7 - Crest of dam as viewed from left abutment  
area.



PHOTO NO. 8 - View of sluiceway exit box. Note debris lining channel.



PHOTO NO. 9 - View of Sawmill River downstream of Locks Pond Road.





PHOTO NO. 10 - Northeast view of Lake Wyola.



PHOTO NO. 11 - Southeast view of Lake Wyola.



PHOTO NO. 12 - Overall view of downstream face of dam.



PHOTO NO. 13 - Downstream face of dam as viewed from left abutment area showing profile of stone wall. Scale = 6 feet.

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

JOB Dance

SUBJECT Wyola

CLIENT Corps

built 1940<sup>2</sup> to replace 1863 dam washed-out in 1738.

Hydraulic Height = 24'

Spillway 229'

$\therefore \text{stop} = 1350 \text{ a/f}$

Size class = Intermediate.

D-Image Area = 44.86 sq in, 4119 c., 6.435 sq m.

Lake Area = 1.33  $\frac{1}{2}$  in, 128. a.


$E_{100} 840 = 2.46 \quad 228. a.$

Max flood 1938 washed-out old dam.

Water Elev 831±

Outlet side E30 along wall - USGS

spillway 834<sup>±</sup>



12/10/83

M/L

BY FDD




HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

JOB Dams

SUBJECT Wyold

CLIENT Corps

Drainage Area 4,119. a

Storage

	ELEV	D	Gross	Avg - area	Storage	Accum S
Outlet	819.0	0	83.0 <sup>±</sup>	83.	0 d-f	0
Spillway	830.0	11	124.±	104.	1144.	1144.
	831.0		128.	126	126.	1270
	831.5	1.5	136.	132	198.	1468.
	832.2	0.7	137.7	136.8	96	1564.
Top	832.2	1.0	140.	138.7	139.	1703.
Flow	840.6	6.8	228	182.	1251.	2954.
	837.0	3.8	189	165	718	2421.

SIZE CURVES

Intermediate.

Standard Potential Significant.Test Flood

1/2 PMF to PMF.

Appears 5 structures near stream USE 1/2 PMF

76,244

2/17/72

LHA

BY FDD



HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 3 of  
JOB Dams  
SUBJECT Wye  
CLIENT Corps

Drainage Area = 6.44 sq. mi.  
PMF = 1300 cfs/sq. mi. "rolling flat" (pond-swamp st)

$$1/2 PMF = 1300 \times 6.44 \times 1/2 \approx 4200 \text{ cfs}$$

Discharge - Height (Flow thru culvert negligible)

Elev	D	L	C	H <sup>3/2</sup>	Q	Q'	Q <sup>T</sup>
					cfs		cfs
830	0	-	-	0			
831.5	1.5	48	2.65	1.84	234		= 234
832.2	0.7	20	2.68	0.59	31	415	= 446
833.2	1.0	44	2.68	1.0	118	856	= 974
836.0	2.8	210	2.63	4.7	3327		= 4183 $\approx 4200$
837.0	3.8	275	2.63		5358		= 6214
838.0	4.8	280	2.63	10.5	7749		= 8600

Storage - Discharge (adj for base stor)

$$Q_{p1} = 4200 \text{ ELEV } 836.00$$

$$St_{r1} = 1056 \text{ a-f} \times 12^{1/2} \times \frac{1}{4119} = 3.08 \text{ " runoff}$$

$$Q_{p2} = 4200 \times \left(1 - \frac{3.08}{9.5}\right) = 2840 \text{ cfs}$$

$$Elev_2 = 835.5 \pm \quad St_{r2} = 2150 \text{ a-f} - 1144 = 1006$$

$$\text{Avg Stor} = (1056 + 1006) \times \frac{1}{2} = 1033 \text{ a-f}$$

$$Q_{p3} = 4200 \left(1 - \frac{3.01}{9.5}\right) = 2870 \text{ cfs} \quad \text{Flows over top of dam}$$

At 8' HUMP - Str H  $H_w/D = 12/8 = 1.5 \quad Q = 600$   
water will flow over roadway

78,244.1

12/19/78

WIA

FDD

**HH  
&B**HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

SHEET NO. 4 of

JOB DamsSUBJECT WyldCLIENT corpsDim. Failure Analysis

$$S = 1565 \text{ df}$$

$$W_b = 140' \times .4 = 56'$$

$$Q_{P1} = 8/27 \times 56 \times \sqrt{32.2} \cdot (14)^{3/2} \approx 4933 \text{ cfs} > 281$$

St. 9+00

$$S = 0.0111$$

narrow stream, rocky btm - sides wooded  
flood plain  $n = 0.06$ .

$$L = 10' \quad W_P = 250 \quad A = 860 \quad R = 3.44$$


$$V = \frac{1.486}{.06} (.01)^{1/2} (3.44)^{.67} = 2.48 (2.29) = 5.67$$

$$Q = 4820 \text{ cfs} < \text{reqd}$$

$$L = 12' \quad W_P = 300 \quad A = 860 + 520 \quad R = 4.6$$

$$V = 2.48 (2.78) = 6.89$$

$$Q = 9514 \text{ cfs} > \text{reqd}$$



See curve of backwater - next sheet.

Sta 2+00 At Quarter Q = 600 cfs

$$Q_{road} = 4933 - 600 = 4333 \text{ cfs}$$

$$D = 4' \quad S = 0.0171 \quad WP = 180' \quad A = 360 \quad R = 2$$

$$V = \frac{1.486}{.06} (1.1)(1.59) = 4 \text{ fps}$$


$$Q = 1418 \text{ cfs}$$

$$D = 6' \quad WP = 260' \quad A = 360 + 320 = 680 \quad R = 2.62 \quad V = 4.7$$

$$Q = 3211$$

$$D = 8' \quad WP = 330' \quad A = 680 + 520 = 1200 \quad R = 3.6 \quad V = 5.9$$

$$Q = 7067$$



$Q \times 1000 \text{ cfs}$

$$\text{Elev } 835.5, \quad Q = 4933 \text{ cfs}$$

$$\text{Storage} = V_1 = \frac{2200 + 1700}{2} (700) \left( \frac{1}{43560} \right) = 23.3 \text{ af OK}$$

$$Q_{P2} = 4933 \left( 1 - \frac{23.3}{1570} \right) \approx 4860 \text{ cfs}$$

$$V_2 = \frac{2200 + 900}{2} (700) \left( \frac{1}{43560} \right) \approx 25 \text{ af}$$

$$(V_1 + V_2) \left( \frac{1}{2} \right) = 24.2$$

$$Q_{P3} = 4933 \left( 1 - \frac{24.2}{1570} \right) = 4857 \text{ cfs}$$



7B.244.1

12/19/78

MA

FDD

HH  
&BHAYDEN, HARDING & BUCHANAN, INC  
CONSULTING ENGINEERS  
BOSTON MASSACHUSETTS

SHEET NO.

6 of 6

JOB Dams

SUBJECT Wyold

CLIENT Corps

Sta 14+00  $S = 10/500' = 0.02''$ 

$$D = 10' \quad WP = 170' \quad A = 35 \times 20 = 700 \text{ sq ft} \quad R = 4.12$$

$$V = \frac{1.486}{.06} (-.1414)(2.58) = 3.5( ) = 9$$

$$Q = 6325 \text{ cfs} > \text{reqd } 4857$$

$$D = 8' \quad WP = 150' \quad A = 550 \text{ sq ft} \quad R = 3.67$$

$$V = \frac{1.486}{.06} (2.32)(.1414) = 8.4$$

$$Q = 4584 \quad \text{say OK}$$

Elev

$$Vol = \frac{550 + 900}{2} \times \frac{500}{43560} = 8.3 \text{ a-f}$$

$$Q_{P2} = 4857 \left(1 - \frac{8.3}{1570}\right) = 4831 \text{ cfs}$$

Between Dam & Sta 14+00 5 homes would be damaged - loss of life could result.


Below 14+00 homes are above stream bed & stream flood plain widens out. Just prior to its junction with Red Brook, 2 more homes are close to the stream. They would be damaged and loss of life could occur, at Sta 32+00±.

78.244.1  
 2/19/78  
 MA  
 PDD



HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS

SHEET NO. 7 of 7  
 JOB Dams  
 SUBJECT Wyold  
 CLIENT Corps





NO 78,244,1  
 12/17/78  
 m  
 BY FDD



HAYDEN, HARDING & BUCHANAN, INC  
 CONSULTING ENGINEERS  
 BOSTON, MASSACHUSETTS

JOB Dams SHEET NO. 8 of 1  
 SUBJECT Wyob  
 CLIENT corps




No. 7A, 249.1  
 3/16/79  
 MA  
 BY FOD



HAYDEN, HARDING & BUCHANAN, INC.  
 CONSULTING ENGINEERS  
 BOSTON MASSACHUSETTS

SHEET NO. 9  
 JOB Dams  
 SUBJECT Wyclo  
 CLIENT Corp

# Discharge Thru 3.5' x 3.5' culvert




$K_c = .9$

Res

To Pipe

EL	Q	Q'	HV/D	D	EI	MAX'EL	HV/D	QP	QR
833.2	975	1100	3	24	841	830	1.56	600	500±
832.2	450	600	1.35		828.3				
831.5	200	300	0.77	6.16	823.7				
	200	150	.5	4	821.5				
		175	.6	5	822.5				



EL	HW-TW=H	n=.024 3.6" CMP	H	ELEV	EL'	Q <sub>3.6"</sub> n=.024	Q <sub>n=.015</sub>
833.2	3.2	125	6'	836 > 833.2		0	
832.2	4.0	150	9	837 > 832.2		0	
831.5	6.8	100	3.8	827.5 < 831.5		> 100	
	10	150	8	829.5 < 831.5		> 150	
	9	175	11	831.5 = 831.5		175 ± 280	
Inlet Control							
	HW/D	Q <sub>P</sub> n=.024	Q' n=.015				
830	2.6	140	224				
828	2.0	110	176				
825	1.14	60	96				
824	0.86	42	67				
822	0.29	9	15				

NO. 78.244.1  
3/16/79  
MA  
BY PDD




HAYDEN, HARDING & BUCHANAN, INC.  
CONSULTING ENGINEERS  
BOSTON MASSACHUSETTS

SHEET NO. 10


JOB - Dams  
SUBJECT Wyold  
CLIENT Corps

### 3.5 x 3.5 Culvert Discharge

HEAD Elev



Actual flow will vary. Grille clogging will significantly reduce outflow. Backwater from B' ACCMP will reduce flow. Assumes valve fully open. -c



SHUTESBURY MASSACHUSETTS  
DATE FEBRUARY 1975

LAKE WYOLA DAM

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

DAYTON, HARDING & BUCHANAN, INC. U.S. ARMY ENGINEER ON NEW ENGLAND  
CONSULTING ENGINEERS  
BOSTON, MASSACHUSETTS

APPENDIX E

INFORMATION AS CONTAINED IN THE  
NATIONAL INVENTORY OF DAMS

77-27  
1000

# INVENTORY OF DAMS IN THE UNITED STATES

STATE	FEDERATION	CONGR. DIST.	STATE	COUNTY	DIST.	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE
WA	510	REF	WA	011	01	LAKE WYOLA DAM	4230.1	7226.2	23FEB79

POPULAR NAME	NAME OF IMPROVEMENT
LUCKS POND	LAKE WYOLA

NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	POPULATION
SHUTESHURY	600

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRAINING HEIGHT	HYDRAULIC HEIGHT	IMPOUNDING CAPACITIES (ACRES-FT.)
REFLECT	1943	R	14	14	1703

DIST OWN FED R PRV/FED SCS A VER/DATE  
NED N N N 07MAR79

REMARKS

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

OWNER	ENGINEERING BY	CONSTRUCTION BY
TOWN OF SHUTESHURY	UNKNOWN	UNKNOWN

REGULATORY AGENCY

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
HAYDEN HARRING + RUCHANAN, INC	27NOV76	PUBLIC LAW 92-367

REMARKS



**END**

**FILMED**

**8-85**

**DTIC**